

STATE OF KANSAS
KANSAS CORPORATION COMMISSION
CONSERVATION DIVISION
130 South Market - Room 2078
Wichita, Kansas 67202

FORM CP-1 (3/92)

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 5135-23915 0000 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR Thomas Castelli Castelli Exploration, Inc. KCC LICENSE # 31021
(owner/company name) (operator's)

ADDRESS 9500 Westgate Dr. #101 CITY Oklahoma City

STATE Oklahoma ZIP CODE 73162 CONTACT PHONE # (405) 722-5511

LEASE Stoecklein WELL# 1 SEC. 28 T. 18s R. 24 East (West)

110'w CN/2-NW - NW SPOT LOCATION/QQQQ COUNTY Ness

330 FEET (in exact footage) FROM S (circle one) LINE OF SECTION (NOT Lease Line)

550 FEET (in exact footage) FROM E/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL D&A SWD/ENHR WELL DOCKET# _____

CONDUCTOR CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

SURFACE CASING SIZE 8 5/8 SET AT 201.30 CEMENTED WITH 130 SACKS

PRODUCTION CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: _____

ELEVATION 2303/2311 T.D. 4390 PBDT _____ ANHYDRITE DEPTH 1578-1615
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING (1st Plug @1600' w/50sks)(2nd Plug @900' w/80sks)

(3rd Plug @230' w/40sks)(4th Plug @40' w/10sks)(10sks In Mouse Hole)(15sks In Rat Hole)

205sks Total 60/40 Poz 6%Gel w/1#ES/sk Completed @ 8:30PM 11/16/95 By Allied Cementing
(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? Yes

If not explain why? _____

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Thomas Alm PHONE# 913 625-5183

ADDRESS 1922 Whittier City/State Hays, Kansas 67601

PLUGGING CONTRACTOR Discovery Drilling Co., Inc. KCC LICENSE # 31548
(company name) (contractor's)

ADDRESS P.O. Box 763 Hays, Kansas 67601 PHONE # (913) 623-2920

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) 8:30PM 11/16/95

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE 1/24/96 AUTHORIZED OPERATOR/AGENT: Thomas P. Alm
(signature)

*Rec'd
1-24-96*