

Exception from KSCNA JP 9/13/2012
ok'd to accept old forms per SB

D.2

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION
Please TYPE Form and File ONE Copy

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

API # 15 - none 035-19340-0000 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date spud 11/24/50

Well Operator: Ron Whiteman dba/Gen-Dor Oil Company KCC License #: 9576
(Owner / Company Name) (Operator's)

Address: 8135 281st rd City: Cambridge

State: Kansas Zip Code: 67023 Contact Phone: (620) 467-2615

Lease: Stolp Well #: 4 Sec. 20 Twp. 30 S. R. 7 East West

SE SE SE Spot Location / QQQQ County: Cowley

~~800~~ 324 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

~~800~~ 311 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 8 5/8 Set at: 45 Cemented with: 40 Sacks

Production Casing Size: 5 1/2 Set at: 3009 Cemented with: 75 Sacks

List (ALL) Perforations and Bridgeplug Sets: perms from 2873 to 2885 (MISS) CIBP set at 2910

RECEIVED
SEP 13 2012
KCC WICHITA

Elevation: 1469 (G.L. / K.B.) T.D.: 3260 P.B.T.D.: 2965 Anhydrite Depth: unknown
(Stone Coral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): fill bottom of hole with sand to 50 ft above perms and dump-bail 6sx cement on top, shoot and pull pipe, for top plug circulate cement from 50 ft below surface pipe or 350 ft to surface

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? _____

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Ronnie Whiteman (cell # 620-222-4316)

Phone: (620) 467-2615

Address: 8135 281st rd City / State: Cambridge, Kansas 67023

Plugging Contractor: Gen-Dor Oil Company KCC License #: 9576
(Company Name) (Contractor's)

Address: 8135 281st rd Phone: (620) 467-2615

Proposed Date and Hour of Plugging (if known?): will call in to district office

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent
Date: 9-12-12 Authorized Operator / Agent: Ronnie Whiteman
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202



Mark Sievers, Chairman
Thomas E. Wright, Commissioner
Shari Feist Albrecht, Commissioner

Corporation Commission

Sam Brownback, Governor

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

WHITEMAN, RON DBA GEN-DOR OIL CO.
8135 281ST RD
CAMBRIDGE, KS 67023-9308

September 14, 2012

Re: STOLP #4
API 15-035-19340-00-00
20-30S-7E, 324 FSL 311 FEL
COWLEY COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division has received your plugging proposal, form CP-1, for the above well and has reviewed the proposal for completeness. The central office will now forward your CP-1 to the district office listed below for review of the proposed plugging method. **Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit in accordance with K.A.R. 82-3-600.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. This notice in no way constitutes authorization to plug the above well by persons not having legal rights of ownership or interest in the well.

This notice is void after March 13, 2013. The CP-1 filing does not bring the above well into compliance with K.A.R. 82-3-111 with regard to the Commission's temporary abandonment requirements.

Sincerely,

Steve Bond
Production Department Supervisor

District: #2
3450 N. Rock Road, Suite 601
Wichita, KS 67226
(316) 630-4000