


15-135-20827-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD



Locate well correctly on above
Section Plot

Ness County. Sec 28 Twp 18S Rge. 24W (E) W (W)
Location as "NE/CNW/SW" or footage from lines C SW/4 SW/4
Lease Owner Walters Drilling Co.
Lease Name Litchfield Well No. #1
Office Address 400 Insurance Building, Wichita, Kansas 67208
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed Jan. 11 19 74
Application for plugging filed May 14 19 76
Application for plugging approved May 24 19 76
Plugging commenced March 16 19 76
Plugging completed June 9 19 76
Reason for abandonment of well or producing formation No longer economical

If a producing well is abandoned, date of last production Feb. 18 19 76
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey
Producing formation Cherokee Sand Depth to top Bottom Total Depth of Well 4373' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	234'	None
				5 1/2"	4372'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Allied Cementing Co., Inc., P. O. Box 31, Russell, Kansas 67665 pumped 25 sacks common cement, 4% gel down 5 1/2" casing at 1300 psi. Followed with 1 1/2 sacks of cottonseed hulls and 30 sacks of gel. Mixed 50 sacks common cement, 4% gel, and pumped down 5 1/2" casing at 1250 psi.

7-20-76

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Allied Cementing Company, Inc.
Address P. O. Box 31, Russell, Kansas 67665

STATE OF Kansas COUNTY OF Sedgwick ss.
Robert F. Walters, Managing Partner (emp/ty of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Robert F. Walters, Mgm. Partner, Walters Drilling Co.
400 Insurance Bldg. (Address) Wichita, Kans. 67202

Sworn to before me this 19th day of July, 19 76

Laverne G. Detert
Notary Public.



15-135-20827-0000
 GABBERT-JONES, INC.
 WICHITA, KANSAS
 DRILLERS' WELL LOG


LITCHFIELD #1
 C SW SW
 Section 28-18S-24W
 Ness County, Kansas

Commenced: December 6, 1973
 Completed: December 20, 1973

OPERATOR: WALTERS DRILLING CO.

Depth From	To	Formation	Remarks
0	245	Surface clay-sand-shale	Ran 6 jts of used 28# 8 5/8"
245	800	Shale-sand	csg. set @ 242' cemented w/
800	1047	Shale-shells	175 sks common, 2% Gel, 3% CC
1047	1592	Shale-sand-redbed	P.D. 3 AM 12/6/1973
1592	1636	Anhydrite	Cement Circ.
1636	2200	Shale	
2200	3953	Lime-shale	
3953	4317	Lime	
4317	4327	Core #1	
4327	4332	Core #2	
4332	4339	Sand	
4339	4355	Cong-Chert	
4355	4373	Lime-chert	Ran 138 jts of used 15 1/2 &
4373	TD		14# 5 1/2" csg set @ 4372' cemented w/125 sks 50/50 Posmix, Salt Sat on bottom D.V. Tool @ 1400' cemented w/325 sks Halcolite w/5# Gilsonite per sack P.D. @ 2:30 PM 12/20/1973

I, James S. Sutton, II, certify this is a correct copy of the Drillers' Log for the well drilled in the C SW SW, Section 28-18S-24W, Ness County, Kansas, to the best of my knowledge and belief.


 James S. Sutton, II

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

Before me, the undersigned, a Notary Public, within and for said County and State, on this 28th day of December, 1973, personally appeared James S. Sutton, II, to me personally known to be the identical person who executed the within and foregoing instrument and acknowledged to me that he executed the same as his free and voluntary act and deed for the uses and purposes therein set forth.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal the day and year last above written.
 My Commission expires Nov. 29, 1975


 Marjorie Hall, Notary Public

