

Kansas Corporation Comm.  
Wichita State Office Bldg.  
130 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER S135-23915 0000

LEASE NAME Stoecklein

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER 1

4950 Ft. from S Section Line

4730 Ft. from E Section Line

LEASE OPERATOR Castelli Exploration, Inc.

SEC. 28 TWP. 18S RGE. 24 (X) or (W)

ADDRESS 9500 Westgate Dr. #101

COUNTY Ness

PHONE# (405) 722-5511 OPERATORS LICENSE NO. 31021

Date Well Completed 11/16/95

Character of Well D&A

Plugging Commenced 5:45PM 11/16/95

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 8:30PM 11/16/95

The plugging proposal was approved on November 15, 1995

by Richard Lacey (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? \_\_\_\_\_

Producing Formation None Depth to Top \_\_\_\_\_ Bottom T.D. 4390'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		0	201	8 5/8	201.30	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to \_\_\_\_\_ feet each set.  
1st Plug @1600' w/50sks 10sks In Mouse Hole Circulated 1st Plug 15 Minutes w/55 Vis Mud  
2nd Plug @900' w/80sks 15sks In Rat Hole plugs displaced with mud.  
3rd Plug @230' w/40sks  
4th Plug @40' w/10sks 205sks Total 60/40 Poz 6 3/4 Gelw/1 #FS/sk By Allied Completed 8:30PM 11/16/95  
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Discovery Drilling Co., Inc. License No. 31021

Address P.O. Box 763 Hays, Kansas 67601

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Castelli Exploration, Inc.

STATE OF Oklahoma COUNTY OF Oklahoma, ss.

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed: the same are true and correct, so help me God.

(Signature) Thomas P. Pruitt

(Address) 9500 Westgate Dr. #101

SUBSCRIBED AND SWORN TO before me this 24th day of January, 1996

Diana L. Price  
Notary Public

My Commission Expires: 2-10-97