

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-135-20,604-0000

LEASE NAME Norton

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER "B"

3450 Ft. from S Section Line

3450 Ft. from E Section Line

LEASE OPERATOR Pickrell Drilling Co., Inc.

SEC. 12 TWP. 18 RGE. 26 (E) or (W)

ADDRESS Box 1303, Great Bend, Ks. 67530

COUNTY Ness

PHONE# (913) 798-7713 OPERATORS LICENSE NO. 4123

Date Well Completed \_\_\_\_\_

Character of Well oil

Plugging Commenced 9-6-90

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 9-13-90

The plugging proposal was approved on August 30, 1990 (date)

by Richard Lacey (KCC District Agent's Name).

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? With application

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 4500'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	263'	None
				5-1/2"	4499'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Dumped sand to 4300' and 5 sacks cement. Shot casing. at 1011'. Allied plugged well 140 sacks 60/40 pozmix cement with 6% gel down the 5-1/2" casing with 300 psi shutin pressure and 140 sacks down the annulus with 100 psi shutin pressure.

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111

Address Box 698, Great Bend, Kansas 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Pickrell Drilling Co., Inc.

STATE OF Kansas COUNTY OF Barton, ss.

James W. Rockhold (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) James W. Rockhold

(Address) Box 698, Great Bend, Ks. 67530

9-18-90  
SEP 18 1990 SUBMITTED AND SWORN TO before me this 17th day of September, 19 90

CONSERVATION DIVISION  
Wichita, Kansas

My Commission Expires:



Iona M. Leatherman  
Notary Public