

STATE OF KANSAS  
STATE CORPORATION COMMISSION


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Comanche County, Sec. 14 Twp. 34S Rge. 20W  
Location as "NE/CNW/SW" or footage from lines C-SW SE

Lease Owner K. R. M. Petroleum Corporation  
Lease Name G. C. Lemon Well No. 4

Office Address Guaranty Bank Bldg., 817 17th St., Denver,  
Character of Well (Completed as Oil, Gas or Dry Hole) CO 80202  
Dry Hole



Locate well correctly on above  
Section Plot

Date Well completed April 20, 1979  
Application for plugging filed Verbal Application  
Application for plugging approved Verbal Approval  
Plugging commenced April 20, 1979  
Plugging completed April 20, 1979  
Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_  
19 \_\_\_\_\_

Was permission obtained from the Conservation Division or  
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Wm. T. Owen  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4,830'  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE   | PUT IN | PULLED OUT |
|-----------|---------|------|----|--------|--------|------------|
|           |         |      |    | 8-5/8" | 793'   | None       |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with heavy rotary mud from 4,830 ft. (rotary total depth) to 780 ft. Set plug at 780 ft. and cemented with 50 sacks cement. Filled hole with heavy rotary mud from 780 ft. to 40 ft. Set solid plug at 40 ft. and cemented to cellar with 12 sacks cement, 3 sacks cement in rat hole.

Plugging operations accomplished utilizing Halliburton Oil Well cementing pump truck through 4 1/2 inch drill pipe.

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Halliburton Services  
410 Union Center Bldg., Wichita, KS 67202

RECEIVED  
STATE CORPORATION COMMISSION  
5-2-79  
MAY 2 1979

STATE OF Kansas COUNTY OF Sedgwick  
Dean Britting, Agent (Signature of owner) ~~XXXXXXXXXXXXXXXXXXXX~~


of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dean Britting  
200 N. Main, Wichita, KS 67202  
(Address)

SUBSCRIBED AND SWORN TO before me this 1st day of May, 19 79

My commission expires July 25, 1982

Elsie Willison  
Elsie Willison - Notary Public.



KANSAS DRILLERS LOG

COMPANY K. R. M. Petroleum Corporation

SEC. 14 T. 34S R. 20W

FARM G. C. Lemon NO. 4

LOC C-SW SE

COUNTY Comanche

ROTARY TOTAL DEPTH 4,830'  
COMM. April 10, 1979 COMP. April 20, 1979  
CONTRACTOR H-30, Inc. (Rig #77)  
ISSUED May 1, 1979

CASING

10 3/4"  
8 5/8" Set at 783' cemented w/875 sxs cement  
5 1/2"  
4 1/2"

ELEVATION 1,766' K.B.

FIGURES INDICATE BOTTOM OF FORMATIONS

|                     |        |
|---------------------|--------|
| Shale               | 784'   |
| Red Bed             | 1,185' |
| Shale               | 2,068' |
| Shale and Lime      | 2,235' |
| Shale and Anhydrite | 2,503' |
| Lime and Shale      | 2,722' |
| Shale and Lime      | 3,439' |
| Lime and Shale      | 4,462' |
| Lime                | 4,830' |
| Rotary Total Depth  | 4,830' |

RECEIVED  
STATE GEOLOGICAL COMMISSION

MAY - 2 1979

CONSERVATION COMMISSION  
GEOLOGICAL DIVISION

I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling reports.

H-30, Inc.

*Alan Britton*

State of Kansas }  
County of Sedgwick } ss:

Subscribed and Sworn to before me a Notary Public in and for said county and state this 1st day of May, 1979.



*Elsie Willison*  
Elsie Willison - Notary Public

My Commission Expires:  
July 25, 1982