

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 9228
Name: Marlin O. Corporation
Address 1: P.O. Box 14630
Address 2: _____
City: Oklahoma City State: OK Zip: 73113 + _____
Contact Person: W.R. (Dick) Lynn
Phone: (405) 478-1900
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (if needed attach another sheet)
Chester Sd Depth to Top: 6126 Bottom: 6139 T.D. 6451
Chester Lm Depth to Top: 5964 Bottom: 5994 T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 189-20850.00.00
Spot Description: _____
SW-SE Sec. 23 Twp. 32 S. R. 35 East West
660.651' Feet from North / South Line of Section
1980.2034' Feet from East / West Line of Section
EPS-KCC
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Stevens
Lease Name: Moore Well #: 2-23
Date Well Completed: 6/16/85
The plugging proposal was approved on: 7-23-12 (Date)
by: Kandy Sullivan (KCC District Agent's Name)
Plugging Commenced: 7-26-12
Plugging Completed: 7-26-12

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
<u>Morrow (5633' 173')</u>	<u>water</u>	-			
<u>Chester Lm (5964' 30')</u>	<u>gas</u>	<u>Surface</u>	<u>9 5/8"</u>	<u>1782'</u>	<u>0-</u>
<u>Chester Sd (6126' 12')</u>	<u>gas, oil</u>	<u>Production</u>	<u>5 1/2"</u>	<u>6450'</u>	<u>2142'</u>

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Marlin Oil set CIBP's @ 5600' + 3200' w/2500s on ea. Shot + pulled 5 1/2 @ 2142' placed plugs as follows: 60 SKS cut. 1810' - 1645', 50 SKS cut. 450' - 315', 10 SKS 40' - 0 w/mud spacing each plug. Cut + Cap 9 5/8 4' below GL.

Plugging Contractor License #: 32833 Name: Sargent + Lillard Casing Pulling Inc.
Address 1: P.O. Box 1450 Address 2: _____
City: Woodward State: OK Zip: 73802-1450
Phone: (580) 254-1881
Name of Party Responsible for Plugging Fees: Marlin Oil Corp.
State of Oklahoma County, Oklahoma, ss. _____
W.R. Lynn (Print Name) Employee of Operator or Operator on above-described well.

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: [Signature] 9/11/12

RECEIVED [Signature]