

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 2/89

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-165-21,496-0000 (of this well).

(This must be listed; if no API# was issued, please note drilling completion date.)

WELL OWNER/OPERATOR Intrepid Production Company OPERATOR'S LICENSE NO. 3922

ADDRESS 718 17th St., Suite 1810, Denver, CO 80202 PHONE # (303) 534-2100
Approx.

LEASE (FARM) Wilson WELL NO. 3-26 WELL LOCATION N/2 S/2 SE COUNTY Rush

SEC. 26 TWP. 16S RGE. 20 (~~E~~)~~XXX~~(W) TOTAL DEPTH 4000' PLUG BACK TD

Check One:

OIL WELL GAS WELL D & A x SWD or INJ WELL DOCKET NO.

SURFACE CASING SIZE 8 5/8" SET AT 277' CEMENTED WITH 150 SACKS

CASING SIZE SET AT CEMENTED WITH SACKS

PERFORATED AT

CONDITION OF WELL: GOOD x POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Circulate heavy mud 20 minutes. 1st plug at 3928'-40 sx. 2nd

plug at 1380'-50 sx. 3rd plug at 720'-60 sx. and 1 sack Flocel. 4th plug at 300'-40 sx. 5th

plug at 40'-10. sx. Rathole-15 sx. All cement 60/40 pozmix, 6% gel, 1 sack Flocel.

(If additional space is needed use back of form.)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? No IS ACO-1 FILED? No
(If not explain.) Sent to operator for completion

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN at 1:30 a.m. on 10-22-89

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE
RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS

Wilmer Dreiling PHONE # (913) 726-4850

ADDRESS 408 Jefferson, Ellis, KS 67637

PLUGGING CONTRACTOR Abercrombie Drilling, Inc. LICENSE NO. 5422

ADDRESS 150 N. Main, Suite, 801, Wichita, KS 67202 PHONE # (316) 262-1841

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT.

SIGNED:

(Operator or Agent)

DATE:

November 9, 1989