

STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

Rev. 6/4/84

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-165-21,463-0000 (of this well)

(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Intrepid Production Company OPERATORS LICENSE NO. 3922

ADDRESS 718 17th Street, Suite 1810, Denver, CO 80202 PHONE # (303) 534-2100

LEASE (FARM) Wilson WELL NO. 2-26 WELL LOCATION SE NE SE COUNTY Rush

SEC. 26 TWP. 16S RGE. 20 ~~XXXX~~(W) TOTAL DEPTH 4000' PLUG BACK TO

Check One:

OIL WELL GAS WELL D & A X SWD or INJ WELL DOCKET NO.

SURFACE CASING SIZE 8 5/8" SET AT 285' CEMENTED WITH 170 SACKS

CASING SIZE SET AT CEMENTED WITH SACKS

PERFORATED AT

CONDITION OF WELL: GOOD X POOR CASING LEAK JUNK IN HOLE

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Circulate heavy mud in hole. 1st plug at 1360'-50 sx. 2nd plug at 680'-80 sx. 3rd plug at 300'-40 sx. 4th plug at 40'-w/wiper plug-10 sx.

Rathole-15 sx. All cement 60/40 pozmix, 6% gel.

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? No IS ACC-1 FILED? NO
(If not, explain) Sent to operator for completion.

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN at 4:00 p.m. on 3-13-89

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Harold Maley

PHONE # (913) 674-5768

ADDRESS 216 E. McFarland, Hill City, KS 67642

PLUGGING CONTRACTOR Abercrombie Drilling, Inc. LICENSE NO. 5422

ADDRESS 150 N. Main, Suite 801, Wichita, KS 67202 PHONE # (316) 262-1841

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: Jack R. Wharton
(Operator or Agent)

DATE 4-05-89