

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 2/89

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-165-21,598-0000 (of this well).

(This must be listed; if no API# was issued, please note drilling completion date.)

WELL OWNER/OPERATOR Argent Energy, Inc. OPERATOR'S LICENSE NO. 30269

ADDRESS 110 S. Main, Suite 510, Wichita, KS 67202 PHONE # (316) 262-5111

LEASE (FARM) Elmore 'A' WELL NO. #2 WELL LOCATION SW NE NW COUNTY Rush

SEC. 26 TWP. 16S RGE. 20 (E) or (W) TOTAL DEPTH 3940' PLUG BACK TD _____

Check One:

OIL WELL _____ GAS WELL _____ D & A X SWD or INJ WELL _____ DOCKET NO. _____

SURFACE CASING SIZE 8 5/8" SET AT 268' CEMENTED WITH 60-40 posmix-170 sx SACKS

CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

PERFORATED AT _____

CONDITION OF WELL: GOOD X POOR _____ CASING LEAK _____ JUNK IN HOLE _____

PROPOSED METHOD OF PLUGGING Fill w/heavy mud; set 1st plug @ 3900' w/50 sx; 2nd plug

@ 1390' w/50 sx; 3rd plug @ 700' w/50 sx; 4th plug @ 300' w/50 sx; 5th plug @ 40' w/wiper

plug w/10 sx; rathole 15 sx; 60-40 posmix 6% gel.

(If additional space is needed use back of form.)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? _____ IS ACO-1 FILED? No

(If not explain.) Sent to Operator to complete

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN 11:00 p.m. 1-18-92

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Harold Maley PHONE # (913) 745-5693 STATE CORPORATION COMMISSION

ADDRESS 216 E. McFarland, Hill City, KS 67642 RECEIVED
JAN 30 1992

PLUGGING CONTRACTOR Abercrombie RTD, Inc. LICENSE NO. 30684 CONSERVATION DIVISION

ADDRESS 150 N. Main, Suite 801, Wichita, KS 67202 PHONE # (316) 262-1841 Wichita, Kansas

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT.

SIGNED: Jack R. Wharton
(Operator or Agent)

DATE: January 28, 1992