

State of Kansas



ROBERT B. DOCKING
DALE E. SAFFELS
JULES V. DOTY
JAMES O. GREENLEAF
RAYMOND B. HARVEY
JACK GLAVES

Governor
Chairman
Commissioner
Commissioner
Secretary
Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg.

212 N. Market

WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Burton of Pickrell Drlg. has this
date requested permission to plug the following described well:

Mr. Burton guarantees payment of the plugging fee.

Operator's full Name: Pickrell Drilling Company

Complete Address: 705 4th Nat'l Bk, Bldg., Wichita, Ks.

Lease Name: Bisagno "A" Well No. 1

Location: SE NE SE Sec. 16 Twp. 16 Rge. 20 (E)(W) X

County: Rush Total Depth 3984 Oil Well

Gas Well Input Well 6WD Well D & A X Lost Hole

Mr. Burton was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 720' and displace

70 sc cmt thru drill pipe. Heavy mud to 240' set cementing plug and

displace 20 sc cement thru drill pipe. Heavy mud to 40' set cementing

plug, 1/2 sc hulls and 10 sc cement to base of cellar. Plug rat hole

with 2 sc cement.

RECEIVED
STATE CORPORATION COMMISSION

Very truly yours,

OCT 1 - 1968

CONSERVATION DIVISION

Wichita, Kansas

Leo F. Massey
Conservation Division Agent