

15-165-20166-0000

State of Kansas



ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION
 (Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 JUL 11 1968
 CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Gould of Barnett Oil Company has this date requested permission to plug the following described well:

Mr. Gould guarantees payment of the plugging fee.

Operator's full Name: Barnett Oil Co.

Complete Address: 411 First Nat'l Bk. Bldg. Wichita, Ks.

Lease Name: Royce Well No. 1

Location: C SW SW Sec. 5 Twp. 16 Rge. 20 (E)(W) X

County: Rush Total Depth 4110 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Gould was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 1190' and displace
90 sc cement thru drill pipe. Heavy mud to 240' set cementing plug and
displace 25 sc cement thru drill pipe. Heavy mud to 40' set cementing
plug, 1/2 sc hulls and 10 sc cement to base of cellar. Plug rat hole
with 2 sc cement.

Very truly yours,

Ken F. Massey
 Conservation Division Agent