

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg.
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

RECEIVED
OCT 10 1965
STATE CORPORATION COMMISSION

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

STATE CORPORATION COMMISSION
WICHITA, KANSAS

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Buchheister of John O. Farmer, Inc., has this

date requested permission to plug the following described well:

Mr. Buchheister guarantees payment of the plugging fee.

Operator's full Name: John O. Farmer, Inc.,

Complete Address: 370 West Wichita, Russell, Kansas

Lease Name: Ree Well No. 1

Location: NW NW NW Sec. 4 Twp. 16 Rge. 20 (E)(W) X

County Rush Total Depth 3968' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Buchheister was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 600' and
displace 25 sc cement thru drill pipe. Heavy mud to 210' set cementing
plug and displace 20 sc cement thru drill pipe. Heavy mud to 40' set
cementing plug, 1/3 sc hulls and 8 sc cement to base of cellar. Plug
rat hole with 2 sc cement.

Very truly yours,

[Signature]
Conservation Division Agent