

3 021838

API No. 15-001-01161-0000

To:

API NUMBER CONTROL NO. 20000002-077

STATE CORPORATION COMMISSION

NW 1/4 Sec/Twp/Rge S.17-T26-R18E

Wichita State Office Bldg. - PLUGGING SECTION

4569 feet from south section line

130 S. Market, Room 2078

2925 feet from east section line

Wichita, Kansas 67202

TECHNICIAN'S PLUGGING REPORT

Lease/Well# MCKINLEY/MCARTNEY NO77

Operator License # 161

County ALLEN

Operator: STATE OF KANSAS

Well Total Depth 800' feet

Name & FEE FUND PLUGGING

Production Pipe: 5 1/2" Size Feet 800'

Address

Surface Casing: 10" Size Feet

AB oil well x Gas Well SWD Well/ Input Well

D & A

Other well as hereinafter indicated:

Plugging Contractor: SPLANE PULLING AND ROUSTABOUT SERVICE

Lic. # 6372

Address: P.O. BOX 386, CHANUTE, KANSAS 66720

Company to plug at: Hour: 8:00AM Day: 10 Month: 4 2000

Plugging proposal received from CLAYTON P. TITEL

Company Name: KANSAS CORPORATION COMMISSION Phone: 316-432-2300

Were: THIS WELL CONSISTED OF 5 1/2" CASING TO APPROXIMATELY 800' THAT HAD BEEN
CEMENTED IN AT T.D. ONLY. THE PLUGGING PROPOSAL WAS TO PERFORATE THE CASING AND
TO CIRCULATE AS MUCH OF THE WELL AS POSIBLE FULL OF CEMENT.

Plugging Proposal Received by:

CLAYTON P. TITEL

Plugging attended by Agent: All Part

X None

Operations Completed: Hour: 10 Day: 4 Month: 2000

Actual Plugging Report: AS PER INSTRUCTION THE WELL WAS PERFORATED AT 200' AND

AT 500'. 1" PIPE WAS RAN INTO THE 5 1/2" CASING TO 700'. CEMENT WAS PUMPED INTO THE 1"

PIPE UNTIL CEMENT CIRCULATED FROM THE WELL AT SURFACE. THE 1" PIPE WAS REMOVED.

DISPLACEMENT WAS FILLED FROM SURFACE.

RECEIVED
STATE CORPORATION COMMISSION

APR 12 2000

Remarks:

CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this form.)

I DID observe this plugging

Signed:

Clayton P. Titel
TECHNICIAN