

3 021986

15-001-01336-00-00

To:

STATE CORPORATION COMMISSION

Wichita State Office Bldg. - PLUGGING SECTION

130 S. Market, Room 2078

Wichita, Kansas 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 101

Operator: STATE OF KANSAS

Name & STATE FEE FUND PLUGGING

Address _____

AB oil well X Gas Well _____ SWD Well/ Input Well _____

Other well as hereinafter indicated: _____

Plugging Contractor: JAMES D. LORENZ

Lic. # 9313

Address: 543A. 22000RD., CHERRYVALE, KANSAS 67335

Company to plug at: Hour: 1:00P.M. Day: 27 Month: 9 2000

Plugging proposal received from: CLAYTON P. TITEL

Company Name: KANSAS CORPORATION COMMISSION Phone: 316-432-2300

Were: THIS WELL CONSISTED OF 2" CASING TO APPROXIMATELY 800' THAT HAD BEEN

CEMENTED IN AT T.D. ONLY. THE 2" AND 10" ANNULUS WAS OBSTRUCTED WITH CEMENT AT

SURFACE. THE PLUGGING PROPOSAL WAS TO PRFORATE THE 2" CASING AND TO CIRCULATE

AS MUCH OF THE WELL AS POSSIBLE FULL OF CEMENT.

Plugging Proposal Received by: CLAYTON P. TITEL

TECHNICIAN

Plugging attended by Agent: All X Part _____

None _____

Operations Completed: Hour: 3:30P.M. Day: 27 Month: 9 2000

Actual Plugging Report: THE 2" CASING WAS PERFORATED AT 500' AND AT 200. 3/4" PIPE
WAS RAN INTO THE 2" CASING TO 650. CEMENT WAS PUMPED INTO THE 3/4" PIPE UNTIL CEMENT
CIRCULATED FROM THE 2" CASING AT SURFACE. THE 3/4" PIPE WAS REMOVED. DISPLACEMENT
WAS FILLED FROM SURFACE. AN ESTIMATED 195 SACKS OF CEMENT WERE PUMPED INTO THIS
WELL.

RECEIVED
STATE CORPORATION COMMISSION

Remarks: _____

(If additional description is necessary, use BACK of this form.)

OCT 18 2000

I DID observe this plugging.

Signed: _____

Clayton P. Titel
TECHNICIAN

CONSERVATION DIVISION
Wichita, Kansas

NB