

3 021983

To:

STATE CORPORATION COMMISSION

Wichita State Office Bldg. - PLUGGING SECTION

130 S. Market, Room 2078

Wichita, Kansas 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 101

Operator: STATE OF KANSAS

Name & STATE FEE FUND PLUGGING

Address _____

AB oil well X Gas Well _____ SWD Well/ Input Well _____

Other well as hereinafter indicated: _____

Plugging Contractor: JAMES D. LORENZ

Lic. # 9313

Address: 543A. 22000RD., CHERRYVALE, KANSAS 67335

Company to plug at: Hour: 1:00P.M. Day: _____ 21 Month: 9 2000

Plugging proposal received from: CLAYTON P. TITEL

Company Name: KANSAS CORPORATION COMMISSION Phone: 316-432-2300

Were: THIS WELL CONSISTED OF 2" CASING TO APPROXIMATELY 800' THAT HAD BEEN CEMENTED IN AT T.D. ONLY. THE PLUGGING PROPOSAL WAS TO CIRCULATE AS MUCH OF THE WELL AS POSSIBLE FULL OF CEMENT.

Plugging Proposal Received by: CLAYTON P. TITEL

TECHNICIAN

Plugging attended by Agent: All X Part _____

None _____

Operations Completed: Hour: 3:00P.M. Day: _____ 14 Month: 9 2000

Actual Plugging Report: 3/4" PIPE WAS RAN INTO THE 2" CASING TO 525'. CEMENT WAS

PUMPED INTO THE 3/4" PIPE UNTIL CEMENT CIRCULATED FROM THE 2" CASING AT SURFACE.

THE 3/4" PIPE WAS REMOVED. 1 1/4" PIPE WAS RAN INTO THE 2" AND 10" ANNULUS TO 500'.

CEMENT WAS PUMPED INTO THE 1 1/4" PIPE UNTIL CEMENT CIRCULATED FROM THE 10"

SURFACE CASING AT SURFACE. THE 1 1/4" PIPE WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE.

Remarks: _____

(If additional description is necessary, use BACK of this form.)

I DID observe this plugging.

Signed:

Clayton P. Titel
TECHNICIAN

RECEIVED
STATE CORPORATION COMMISSION

OCT 11 2000

CONSERVATION DIVISION
Wichita, Kansas