

3 021920

15-001-01278-0000

To:

API NUMBER

CONTROL NO. 20000033 - 003

STATE CORPORATION COMMISSION

NE 1/4

Sec/Twp/Rge S.18-T.26S.-R.18E.

Wichita State Office Bldg. - PLUGGING SECTION

3177 feet from south section line

130 S. Market, Room 2078

549 feet from east section line

Wichita, Kansas 67202

TECHNICIAN'S PLUGGING REPORT

Lease/Well#

FRAKER NO.3

Operator License #

101

County

ALLEN

Operator: STATE OF KANSAS

Well Total Depth 800'

feet

Name & STATE FEE FUND PLUGGING

Production Pipe: 2"

Size Feet 800'

Address

Surface Casing: 10"

Size Feet ?

AB oil well ☒ Gas Well ☐ SWD Well/ Input Well ☐

D & A

Other well as hereinafter indicated:

Plugging Contractor: JAMES D. LORENZ

Lic. #

9313

Address: 543A 22000 RD., CHERRYVALE, KANSAS 67335

Company to plug at: Hour: 1:00P.M. Day:

5 Month:

7

2000

Plugging proposal received from CLAYTON P. TITEL

Company Name: KANSAS CORPORATION COMMISSION

Phone:

316-432-2300

Were: THIS WELL CONSISTED OF 2" CASING TO APPROXIMATELY 800" THAT

HAD BEEN CEMENTED IN AT T.D. ONLY. THE INSIDE OF THE 2" CASING WAS OBSTRUCTED

BY ACCMULATED SEDIMENTS. THE PLUGGING PROPOSAL WAS TO DRILL OUT THE 2"

CASING AND TO CIRCULATE AS MUCH OF THE WELL AS POSSIBLE FULL OF CEMENT.

Plugging Proposal Received by:

CLAYTON P. TITEL

Plugging attended by Agent:

All

☒

Part

TECHNICIAN

None

Operations Completed: Hour: 4:00P.M. Day:

5 Month:

7

2000

Actual Plugging Report:

THE 2" CSING WAS DRILLED OUT TO 550'. 3/4" PIPE

WAS RAN INTO THE 2" CASING TO 550'. CEMENT WAS PUMPED INTO THE 3/4"

PIPE UNTIL CEMENT CIRCULATED FROM THE 2" CASING AT SURFACE. THE 3/4"

WAS REMOVED. 1" PIPE WAS RAN INTO THE 2" AND 10" ANNULUS TO 625'. CEMENT

WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE 10"

SURFACE CASING AT SURFACE. THE 1" PIPE WAS REMOVED. DISPLACEMENT WAS

FILLED FROM SURFACE.

Remarks:

(If additional description is necessary, use BACK of this form.)

DID

observe this plugging

Signed:


 TECHNICIAN

 RECEIVED
 STATE CORPORATION COMMISSION

AUG 2 2000

 CONSERVATION DIVISION
 WICHITA, KANSAS

