

3 021959

To:

STATE CORPORATION COMMISSION

Wichita State Office Bldg. - PLUGGING SECTION

130 S. Market, Room 2078

Wichita, Kansas 67202

TECHNICIAN'S PLUGGING REPORT

Operator License #

101

Operator: STATE OF KANSAS

Name & STATE FEE FUND PLUGGING

Address

AB oil well ☒ Gas Well ☐ SWD Well/ Input Well ☐

Other well as hereinafter indicated:

Plugging Contractor: JAMES D. LORENZ

Lic. #

9313

Address: 543A 22000 RD., CHERRYVALE, KANSAS 67335

Company to plug at: Hour: 10:30A.M. Day: 23 Month: 8 2000

Plugging proposal received from CLAYTON P. TITEL

Company Name: KANSAS CORPORATION COMMISSION

Phone:

316-432-2300

Were: THIS WELLCONSISTED OF 2" CASING TO APPROXIMATELY 800' THAT

HAD BEEN CEMENTED IN AT T.D. ONLY. THE PLUGGING PROPOSAL WAS TO

CIRCULATE AS MUCH OF THE WELL AS POSSIBLE FULL OF CEMENT.

Plugging Proposal Received by:

CLAYTON P. TITEL

Plugging attended by Agent: All ☒ Part ☐

TECHNICIAN

None ☐

Operations Completed: Hour: 1:00P.M. Day: 23 Month: 8 2000

Actual Plugging Report: 3/4" PIPE WAS RAN INTO THE 2" CASING TO 580'.

CEMENT WAS PUMPED INTO THE 3/4" PIPE UNTIL CEMENT CIRCULATED FROM

THE 2" CASING AT SURFACE. THE 3/4" PIPE WAS REMOVED. 1" PIPE WAS RAN INTO

THE 2" AND 10" ANNULUS TO 525'. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL

CEMENT CIRCULATED FROM THE 10" SURFACE CASING AT SURFACE. THE 1" PIPE

WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE.

Remarks:

(If additional description is necessary, use BACK of this form.)

I DID observe this plugging

Signed:

Clayton P. Titel
TECHNICIAN

RECEIVED

STATE CORPORATION COMMISSION

SEP 13 2000

CONSERVATION DIVISION
Wichita, Kansas