

3 021974

15-001-01318-0020

To:

STATE CORPORATION COMMISSION

Wichita State Office Bldg. - PLUGGING SECTION

130 S. Market, Room 2078

Wichita, Kansas 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 101Operator: STATE OF KANSASName & STATE FEE FUND PLUGGING

Address _____

AB oil well X Gas Well _____ SWD Well/ Input Well _____

Other well as hereinafter indicated: _____

Plugging Contractor: JAMES D. LORENZLic. # 9313Address: 543A. 22000RD., CHERRYVALE, KANSAS 67335Company to plug at: Hour: 1:00P.M. Day: _____ 7 Month: 9 2000Plugging proposal received from: CLAYTON P. TITELCompany Name: KANSAS CORPORATION COMMISSION Phone: 316-432-2300Were: THIS WELL CONSISTED OF 2" CASING TO APPROXIMATELY 800' THATHAD BEEN CEMENTED IN AT T.D. ONLY. THE PLUGGING PROPOSAL WAS TOCIRCULATE AS MUCH OF THE WELL AS POSSIBLE FULL OF CEMENT.

Plugging Proposal Received by:

CLAYTON P. TITEL

Plugging attended by Agent: All _____ Part _____

TECHNICIAN

None XOperations Completed: Hour: 4:00P.M. Day: _____ 7 Month: 9 2000Actual Plugging Report: 3/4" PIPE WAS RAN INTO THE 2" CASING TO 800'.CEMENT WAS PUMPED INTO THE 3/4" PIPE UNTIL CEMENT CIRCULATED FROMTHE 2" CASING AT SURFACE. THE 3/4" PIPE WAS REMOVED. 1" PIPE WAS RAN INTOTHE 2" AND 10" ANNULUS TO 660'. CEMENT WAS PUMPED INTO THE 1" PIPE UNTILCEMENT CIRCULATED FROM THE 10" SURFACE PIPE AT SURFACE. THE 1" PIPEWAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE.

Remarks: _____

(If additional description is necessary, use BACK of this form.)I DID NOT observe this plugging.

Signed:

Clayton P. Titel
TECHNICIANRECEIVED
STATE CORPORATION COMMISSION
SEP 18 2000
CONSERVATION DIVISION
Wichita, Kansas