

3 022180

15- 001-01518-00-00

To:

API NUMBER CONTROL NO.20020021-001

STATE CORPORATION COMMISSION

NW,SE,SW 1/4 Sec/Twp/Rge S.18-T.26S.-R.18E.

Wichita State Office Bldg. - PLUGGING SECTION

663 feet from south section line

130 S. Market, Room 2078

3685 feet from east section line

Wichita, Kansas 67202

TECHNICIAN'S PLUGGING REPORT

Lease/Well# BARNETT II NO.37

Operator License # 101

County ALLEN

Operator: STATE OF KANSAS

Well Total Depth 800' feet

Name & FEE FUND PLUGGING

Production Pipe: 2" Size Feet 800'

Address

Surface Casing: 8" Size Feet ?

AB oil well ☒ Gas Well ☐ SWD Well/ Input Well ☐D & A ☐

Other well as hereinafter indicated:

Plugging Contractor: KEPLEY WELL SERVICE

Lic. # 30670

Address: 19245 FORD ROAD, CHANUTE, KANSAS 66720

Company to plug at: Hour: 3:30P.M. Day: 28 Month: 9 2001

Plugging proposal received from: CLAYTON P. TITEL

Company Name: KANSAS CORPORATION COMMISSION Phone: 316-432-2300

Were: THIS WELL CONSISTED OF 2" CASING TO APPROXIMATELY 800' THAT HAD BEEN
CEMENTED IN AT T.D. ONLY. THE PLUGGING PROPOSAL WAS TO CIRCULATE AS MUCH OF
THE WELL AS POSSIBLE FULL OF CEMENT.

Plugging Proposal Received by:

CLAYTON P. TITEL

Plugging attended by Agent: All ☒ PartTECHNICIAN
None

Operations Completed: Hour: 5:00P.M. Day: 28 Month: 9 2001

Actual Plugging Report: 600' OF 3/4" TUBING WAS PULLED FROM THE WELL. 3/4" PIPE

FROM AN ESTIMATED 800' TO 600' WAS LEFT IN THE WELL. 3/4" PIPE WAS RAN INTO THE 2"

CASING TO 600'. CEMENT WAS PUMPED INTO THE 3/4" PIPE UNTIL CEMENT CIRCULATED

FROM THE 2" CASING AT SURFACE. THE 3/4" PIPE WAS REMOVED. 1" PIPE WAS

RAN INTO THE 2" AND 8" ANNULUS TO 525". CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL

CEMENT CIRCULATED FROM THE 8" SURFACE CASING AT SURFACE. THE 1" PIPE WAS

REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE. 231 SACKS OF CEMENT WERE

Remarks: PUMPED INTO THIS WELL.

(If additional description is necessary, use BACK of this form.)

I DID observe this plugging.

RECEIVED

Signed:


TECHNICIAN

OCT 12 2001

KCC WICHITA

R
OR