

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

3158

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
FEB 18 1971
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name E. K. Edmiston

Complete Address 801 1st Nat'l Bk. Bldg., Wichita, Kansas 67202

Lease Name Bullock Well No. 1

Location NW NW NE Sec. 4 Twp. 16 Rge. (E) (W) 20

County Rush Total Depth 4000'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Glenn & Smith Pipe Pulling

Address Box 156 Ellinwood, Kansas License No. 396

Operation Completed: Hour 10 A Day 17 Month 2 Year 1971

The above well was plugged as follows:

Total Depth 4000' 8 5/8 csg set at 200' cwc

5 1/2 csg set at 4000' cw 90 sk cmt.

5 1/2 csg perf. (3555)

Set 5 1/2 plug at 3500' -poured 10' sd and dumped 5 sk cmt W/dump bailer. (3450-3500)

Recovered 3150' of 5 1/2 csg.

Pumped thru 8 5/8 plug container with 20 sk gel W/3 sk hulls, release plug and

pumped 140 sk 50-50 poz W/4% added gel.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 2/18/71
INV. NO. 3362-W

Signed: Leo Z. Massey
Well Plugging Supervisor