

15-165-20566-0000

R

Form CP-3  
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

JAN 15 1976

CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name The Dane G. Hansen Trust

Complete Address P. O. Box 187, Logan, Kansas

Lease Name Wasinger Well No. 1

Location NW NW NW Sec. 2 Twp. 16 Rge. (E) (W) 20

County Rush Total Depth 3713'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A XX

Other well as hereafter indicated       

Plugging Contractor C & G Drlg.

Address Wichita, Kansas License No.       

Operation Completed: Hour 11:30 P Day 13 Month 1 Year 1976

The above well was plugged as follows:

RTD 3713' 8 5/8 csg set 227' CWC 150 sk. Plg. Mat. 50-50 poz 2% total gel.

Gunned pits, circulated heavy mud; set 50 sk cmt plug at 515' thru drill pipe.

Heavy mud to 215' set 25 sk cmt plug thru drill pipe. Heavy mud to 40' set solid

bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo Messer  
Well Plugging Supervisor

DATE 1-15-76

INV. NO. 25 74-w