

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAR 28 1977
CONSERVATION DIVISION
Wichita, Kansas
(Wichita well)

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 -165 -20,621-0000

Operator's Full Name Dreiling Oil, Inc.
Complete Address Rt #1, Victoria, Kansas 67671
Lease Name Ree Well No. 1
Location SE SE NE Sec. 2 Twp. 16 Rge. (E) (W) 20
County Rush Total Depth 3727'
Abandoned Oil Well Gas Well Input Well SWD Well D & A XX
Other well as hereafter indicated
Plugging Contractor Co. Tools
Address License No.
Operation Completed: Hour 7:45 P Day 26 Month 3 Year 1977

The above well was plugged as follows:

RTD 3727' 8 5/8 csg set 208' cwc 150 sx. Plg. Mat. 50-50 poz 2% total gel.
Gunned pits, circulated heavy mud, set 50 sk cmt plug at 550' thru drill pipe.
Heavy mud to 185' set 25 sk cmt plug thru drill pipe. Heavy mud to 40' set solid
bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Red Massey
Well Plugging Supervisor

DATE 3-28-77
INV. NO. 4974-w