

KANSAS  
STATE CORPORATION COMMISSION

*R*

CONSERVATION DIVISION AGENT'S REPORT

TO:  
Jewel M. Ogden, Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

File No. \_\_\_\_\_ County: Rush

Location: NE NE SE Sec. 2 Twp. 16 Rge. 20 (E) (W)

Name of Field: \_\_\_\_\_ Total Depth: 3719

I have this date completed supervision of plugging of:

Lease Name: Doerr Well No. 1

Operator's Full Name: Morganstern \* Specter

Complete Address: Box 661 Russell, Kans

Plugging Contractor: E & L Pipe Pulling Co

Address: Great Bend, Kans License No. 249

Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereafter indicated: \_\_\_\_\_

Was any delay in plugging operations caused by Conservation Division Agent? Yes \_\_\_ No \_\_\_

If yes how long? \_\_\_\_\_ Reason: \_\_\_\_\_

Operation Completed: Hour 11AM Day 5 Month 10 Year 58

The above well was plugged as follows:

8 5/8" at 1363' circulated with cement - 5 1/2" 3699' with 200 sax cement behind.

Pulled 2460' 5 1/2" to 600', circulated hole with heavy mud ( Gel ) through 5 1/2" - ~~heavy mud~~ displaced 20 sax cement through 5 1/2" at 600', heavy mud to 180', displaced 20 sax cement through 5 1/2", heavy mud to 55', set rock and 10 sax cement to bottom cellar.

Mudding and cementing by E & L Co's pump track.

Signed: *E. H. [Signature]*  
Conservation Division Agent

Reviewed: *J. Lewis Brock*  
Field Supervisor

Remarks:

PLUGGING  
FILE SEC. 2 T. 16 R. 20W  
BOOK PAGE 129 LINE 31

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 21 1958  
CONSERVATION  
Wichita, Kansas