

15-165-28445-0000

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

AUG 28 1972

CONSERVATION DIVISION
Wichita, KansasJ. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name John O. Farmer, Inc.

Complete Address 370 W. Wichita Ave. Russell, Kansas 67665

Lease Name Oelkers Well No. 1

Location NE NE SE Sec. 23 Twp. 16 Rge. (E) (W) 20

County Rush Total Depth 3895'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Co. Tools

Address License No.

Operation Completed: Hour 10:30 A Day 25 Month 8 Year 1972

The above well was plugged as follows:

RTD 3895' 8 5/8 csg set at 229' cwc Cmt. Mat. 50-50 poz cmt W/6% total gel.

Gunned pits, circulated heavy mud, set cementing plug at 600' and displaced 70 sk cmt thru drill pipe. Heavy mud to 215' set cementing plug and displaced 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Ken F. Messing
Well Plugging Supervisor

INVOICED

DATE 8-30-72INV. NO. 6248-10