

15-165-20052-0000

Q

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

AUG 29 1967

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name Raymond Oil Company

Complete Address: 410 4th Nat'l Bk Bldg. Wichita, Kansas

Lease Name Stephens Well No. 1

Location NW SE SW Sec. 23 Twp. 16 Rge. 20 (E) (W) X

County Rush Total Depth 3938

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Co. Tools

Address: License No.

Operation Completed: Hour 12:30 A Day 28 Month 8 Year 1967

The Above well was plugged as follows:

RTD 3938' 8 5/8 csg set at 264' cwc 175 sc.

Gunned pits, circulated heavy mud, set cementing plug at 800' and displaced 100 sc cem.
thru drill pipe. Heavy mud to 250' set cementing plug and displaced 25 sc cement thru
drill pipe. Heavy mud to 40' set cementing plud, 1/2 sc hulls and 10 sc cement to base
of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Geo F. Messing
Well Plugging Supervisor

DATE 8-29-67

INV. NO. 6224-W