

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENCY'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
DEC 21 1977
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 165-20003-0000 (or this well)

Operator's Full Name Frontier Oil Co.
Complete Address 1720 Kansas State Bank Bldg., Wichita, Kansas 67202
Lease Name Kaiser "B" Well No. 1
Location C W/2 NW Sec. 17 Twp. 17 Rge. (E) (W) 16
County Rush Total Depth 3667'
Abandoned Oil Well Gas Well XX Input Well SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Co. Tools by Allied Cementing Co.

Address Russell, Kansas License No.
Operation Completed: Hour 10 A Day 19 Month 12 Year 1977

The above well was plugged as follows:
Total Depth 3667' 8 5/8 csg set 211' cwc 135 sk.
4 1/2 csg set 3212' cw 175 sk cem. Perf. (3088'-3096')
4 1/2 csg DV tool set 1194' cwc 550 sk. No pipe recovered.
Allied Cementing Co. mixed & pumped down 4 1/2 csg with 35 sk ~~cem~~ W/300 lbs hulls -
displaced with 20 sk gel & water & capped with cementing plug & 45 sk cem. & shutin.
SIP 600 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 12-21-77
INV. NO. 6430-W

Signed: Leo Massey
Well Plugging Supervisor