

15-165-20105-0000

Form CP-3
Rev. 6-9-67

KANSAS

Y
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JAN 24 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Frontier Oil Company

Complete Address 1720 Wichita Plaza Wichita, Kansas

Lease Name Scheuerman "C" Well No. 1

Location NW NW NE Sec. 17 Twp. 17 Rge. 16 (E) (W) X

County Rush Total Depth 3663

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Red Tiger Drlg.

Address Wichita, Kansas License No.

Operation Completed: Hour 11:30 A Day 22 Month 1 Year 1968

The above well was plugged as follows:

RTD 3663' 8 5/8 csg set at 211' cwc 140 sc.

Gunned pits, circulated heavy mud, set cementing plug at 500' and displaced 70 Cu. Ft.

cement thru drill-pipe. Heavy mud to 210' set cementing plug and displaced 20 Cu. Ft.

cement thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 Cu. Ft.

cement to base of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *Leo F. Massey*
Well Plugging Supervisor

DATE 1/24/68
INV. NO. 7140-4