

R

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
OCT 21 1977
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15-165-20657-0008 (of this well)

Operator's Full Name Frontier Oil Co.

Complete Address 1720 KSB&T Bldg., Wichita, Kansas

Lease Name Kaiser "B" Well No. 2

Location 165' S of SW SW NW Sec. 17 Twp. 17 Rge. (E) (W) 16

County Rush Total Depth 3620'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Red Tiger Drlg.

Address Wichita, Kansas License No.

Operation Completed: Hour 6 P Day 19 Month 10 Year 1977

The above well was plugged as follows:

RTD 3620' 8 5/8 csg set 277' cwc 160 sk. Plg. Mat. 50-50 poz cem. 2' total gel
Gunned pits, circulated heavy mud, set 50 sk cmt plug at 720' thru drill pipe.
Heavy mud to 240' set 25 sk cmt plug thru drill pipe. Heavy mud to 40' set solid
bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 10-21-77

INV. NO. 6068-W

Signed: Leo Massey
Well Plugging Supervisor