

KANSAS

Form CP-3  
Rev. 6-4-68

R

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15-165-30090-0000 (Conservation Division  
Wichita, Kansas well)

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 17 1978  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Frontier Oil Co.

Complete Address 1720 Kansas State Bank Bldg., Wichita, Kansas 67202

Lease Name Schriner Well No. 1

Location C SE/4 Sec. 18 Twp. 17 Rge. (E) (W) 16

County Rush Total Depth 3648'

Abandoned Oil Well        Gas Well XX Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Co tools by Allied Cementing Co.

Address Same as above License No.       

Operation Completed: Hour 11:20 A Day 16 Month 88 Year 1978

The above well was plugged as follows:

Total Depth 3648' 8 5/8 csg set 213' cwc 135 sk.

4 1/2 csg set 3186' cw 250 sk cem. PFS(3061'-3067')

4 1/2 csg DV tool set 1168' cwc 550 sk. No pipe recovered.

Mixed & pumped down 4 1/2 csg with 50 sk 50-50 poz 2% -displaced with 20 sk gel &

water-released 4 1/2 plg & capped with 40 sk 50-50 poz 2% & shutin. MPP 1200 lbs.

SIP 800 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]  
Well Plugging Supervisor

DATE 8-18-78

INV. NO. 7858-W