

15.165-20386-0000

Form CP-3  
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
APR 19 1971  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Frontier Oil Company

Complete Address 1720 Wichita Plaza Wichita, Kansas 67202

Lease Name Bartel Well No. 1

Location C W/2 NE Sec. 18 Twp. 17 Rge. (E) (W) 16

County Rush Total Depth 3676'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A XX

Other well as hereafter indicated       

Plugging Contractor Red Tiger Drlg.

Address Wichita, Kansas License No.       

Operation Completed: Hour 6.30 A Day 17 Month 4 Year 1971

The above well was plugged as follows:

RTD 3676' 8 5/8 csg set at 209' cwc Gmt. Mat. 50-50 poz W/4% added gel.

Gunned pits, circulated heavy mud, set cementing plug at 420' and displaced 50 sk cmt

thru drill pipe. Heavy mud to 210' set cementing plug and displaced 25 sk cmt thru

drill pipe. Heavy mud to 40' set cementing plug, 1/2 s $\frac{1}{2}$  hulls and 10 sk cmt to base

of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo J. Massey  
Well Plugging Supervisor

DATE 4/20/71

INV. NO. 3569-W