

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

NOV 17 1975

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Frontier Oil Co.

Complete Address 1720 Wichita Plaza, Wichita, Kansas 67202

Lease Name Erni "B" Well No. 1

Location NW SW NW Sec. 18 Twp. 17 Rge. (E) (W) 16

County Rush Total Depth 3640'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Rockhold Engineering

Address Box 698, Great Bend, Kansas 67530 License No. 670

Operation Completed: Hour Day 14 Month 11 Year 1975

The above well was plugged as follows:

Total Depth 3640' 8 5/8 csg set 359' cwc

4 1/2 csg set 3154' cw 150 sk cem.

4 1/2 csg PBTB 2854' & perf. (2819')

Filled 4 1/2 csg W/sd (2854'-2800') dumped 3 sk cem W/dump bailer. (2800'-2730')

Cutoff & recovered 1915' of 4 1/2 csg.

Mixed & pumped down 8 5/8 csg with 20 sk gel & water W/300 lbs hulls -8 5/8 plug

& 60 sk 50-50 poz 2 1/2 -displaced with 5 sk gel & water & capped with 15 sk 50-50

poz 2 1/2 by Allied Cementing Co. PP 200 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 11-17-75

INV. NO. 2262-W