

15-1105-00179-00-01

KANSAS

Form CP-3
Rev. 6-4-68

**STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT**

RECEIVED
STATE CORPORATION COMMISSION

MAR 10 1975

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Frontier Oil Company

Complete Address 1720 Wichita, Plaza, Wichita, Kansas 67202

Lease Name Schriner (OWWO) Well No. 2

Location SW SW SE Sec. 18 Twp. 17 Rge. (E) (W) 16

County Rush Total Depth 3592'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated (OWWO)

Plugging Contractor Co. Tools

Address License No.

Operation Completed: Hour 2 P Day 6⁶ Month ~~1974~~ 3 Year 1975

The above well was plugged as follows:

Total Depth 3592' 8 5/8 csg set 1159' cwc 500 sk.

4 1/2 csg set 3590' cw 250 sk cem.

4 1/2 csg PBTB 3410' with perf. (3335-3341)

Set 4 1/2 wood plug 3300' -poured 20' sd- dumped 3 sk cem W/dump bailer. (3300-3250)

Recovered 2600' of 4 1/2 csg.
Drig mud to 390' -set rock & sand bridge (390-380)

Filled with RM cem. from 380' to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 3/11/75
INV. NO. 981-W

Signed: Rev. F. Massey
Well Plugging Supervisor