

15-135-20741-0000

Form CP-3
Rev. 6-4-68

KANSAS

WJ
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

MAY 2 1973

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Cities Service Oil Company

Complete Address 710 Sutton Place Wichita, Kansas

Lease Name Kanaga Well No. 1

Location C SW NE Sec. 9 Twp. 20 Rge. (E) (W) 23

County Ness Total Depth 4470'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Red Tiger Drilling

Address Wichita, Kansas License No.

Operation Completed: Hour 3:45 P Day 1 Month 5 Year 1973

The above well was plugged as follows:

RTD 4470' 8 5/8 csg set at 523' cwc:

Gunned pits, circulated heavy mud, set cementing plug at 535' and displaced 50 sk
cmt thru drill pipe. Heavy mud to 240' set cementing plug and displaced 25 sk cmt
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to
base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Barry Massey
Well Plugging Supervisor

INVOICED

DATE 5/2/73
INV. NO. 9316-W