

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
APR 17 1969  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Pickrell Drilling Company

Complete Address: 705 4th Nat'l Bank Bldg., Wichita, Kansas 67202

Lease Name Ripple "A" Well No. 1

Location GSE SW Sec. 12 Twp. 20 Rge. (E) (W) 23

County Ness Total Depth 4375'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: GO. Tools

Address: \_\_\_\_\_ License No. \_\_\_\_\_

Operation Completed: Hour 1A Day 14 Month 4 Year 1969

The Above well was plugged as follows:

RTD 4375' 8 5/8 csg set at 249' cwc Cmt. Mat. 50-50 poz cmt. W/6% total gel.

Gunned pits, circulated heavy mud, set cementing plug at 720' and displaced 70 sk cmt.

thru drill pipe. Heavy mud to 240' set cementing plug and displaced 20 sk cmt thru

drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to base

of cellar. Plugged rat hole with 2 sk cmt.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo F. Massey  
Well Plugging Supervisor

INVOICED  
DATE 4/17/69  
INV. NO. 9610-W