

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
FEB 5 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name R. V. Lehner
Complete Address Box 398 Ness City, Kansas
Lease Name Strobel Well No. 4
Location C SE SW Sec. 19 Twp. 20 Rge. (E) (W) 23
County Ness Total Depth 4388'
Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D & A XX
Other well as hereafter indicated _____
Plugging Contractor Strata Drlg.
Address Wichita, Kansas License No. _____
Operation Completed: Hour 5:15A Day 4 Month 2 Year 1970

The above well was plugged as follows:

RTD 4388' 8 5/8 csg set at 288' cwc Cmt. Mat. 50-50 poz 6% gel.

Gunned pits, circulated heavy mud, set cementing plug at 660' and displaced 70 sk
cmt thru drill pipe. Heavy mud to 270' set cementing plug and displaced 20 sk cmt
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to
base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo J. Massey
Well Plugging Supervisor

DATE 2/6/70

INV. NO. 1379-u