

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
NOV 18 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name R. V. Lehner
Complete Address Box 398 Ness City, Kansas 67560
Lease Name Strobel Well No. 3
Location C SE SE Sec. 19 Twp. 20 Rge. (E) (W) 23
County Ness Total Depth 4420'
Abandoned Oil Well XXX Gas Well Input Well SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Forbes Casing Pulling Co.
Address Box 221 Great Bend, Kansas License No. 637
Operation Completed: Hour 12:30 P Day 16 Month 11 Year 1970

The above well was plugged as follows:

Total Depth 4420' 8 5/8 csg set at 288' cwc 160 sk.
5 1/2 csg set at 4367' cw 150 sk cmt.
5 1/2 csg PBTB 4335' with top perf. (4272')
Filled 5 1/2 csg W/sd (4250-4335) Dumped 5 sk cmt W/dump bailer. (4215-4250)
Recovered 900' of 5 1/2 csg.
Pumped thru 8 5/8 plug container with 25 gal W/5 sk hulls, plug and 130 sk reg poz
W/6% total gel. Pres. 550 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo J. Murray
Well Plugging Supervisor

DATE 11/18/70
INV. NO. 2876-W