

R

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

APR 20 1976

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 -1355-21,187 -0000 (of this well)

Operator's Full Name Chief Drlg. Co., Inc.

Complete Address 905 Century Plaza, Wichita, Kansas

Lease Name Strobel Well No. 1

Location SE NE Sec. 19 Twp. 20 Rge. (E) (W) 23

County Ness Total Depth 4480'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Co. Tools

Address License No.

Operation Completed: Hour 4:45 P Day 18 Month 4 Year 1976

The above well was plugged as follows:

RTD 4480' 8 5/8 csg set 293' cwc 200 sk. Plg. Mat. 50-50 poz 2% total gel.

Gunned pits, circulated heavy mud, set 50 sk cmt plug at 500' thru drill pipe.

Heavy mud to 240' set 25 sk cmt plug thru drill pipe. Heavy mud to 40' set solid

bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo Mackey
Well Plugging Supervisor

DATE 4-21-76

INV. NO. 3091-W