

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
OCT 6 1969
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name R. V. Lehner

Complete Address Box 398 Ness City, Kansas

Lease Name Strobel Well No. 2

Location C NW SW Sec. 19 Twp. 20 Rge. (E) (W)23

County Ness Total Depth 4398

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Straja Drlg.

Address Wichita, Kansas License No.

Operation Completed: Hour 10:30A Day 4 Month 10 Year 1969

The above well was plugged as follows:

RTD 4398' 8 5/8 csg set at 288' cwc Cmt. Mat. 50-50 poz cmt. W/6% total gel.

Gunned pits, circulated heavy mud, set cementing plug at 650' and displaced 70 sk cmt thru drill pipe. Heavy mud to 270' set cementing plug and displaced 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 10/6/69

INV. NO. 589-W

Signed: [Signature]
Well Plugging Supervisor