

15-135-20118-0000

Form CP-3
Rev. 6-26-62

KANSAS

SP
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAY 13 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name R. V. Lehner

Complete Address: P. O. Box 398 Ness City, Kansas

Lease Name Strobel Well No. 1

Location C SW NW Sec. 19 Twp. 20 Rge. 23 (E) (W) X

County Ness Total Depth 4491

Abandoned Oil Well X Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Forbes Casing Pulling Inc.

Address: Box 221 Great Bend, Kansas License No. 49

Operation Completed: Hour 2 P Day 8 Month 5 Year 1968

The Above well was plugged as follows:

Total Depth 4491 8 5/8 csg set at 289' cwc 185 sc.

4 1/2 csg set at 4437' cw 125 sc cement.

PBTD 4367 with top perf. at 4354

Filled with sand to 4300' and dumped 4 sc cement with dump bailer.

Recov. 3600' of 4 1/2 csg.

Pumped thru 8 5/8 plg container with 30 sc gel and water W/5 sc hulls., Plug and

150 sc 50-50 poz cement W/4% add. gel. Pumping pres. 750 lbs. SI pres. 300 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 5/15/68

INV. NO. 9938-4

Signed: Geo F. Massey
Well Plugging Supervisor