

KANSAS

Form CP-3
Rev. 6-4-68

f

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENCY'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 135 - 21,401 - 0000 (of this well)

Operator's Full Name Kinderhook Oil & Gas, Inc.

Complete Address 4608 Boulevard Place, Des Moines, Iowa

Lease Name Strobel "A" Well No. 1

Location 150' N & 50' W of C SW NW Sec. 19 Twp. 20 Rge. (E) (W) 23

County Ness Total Depth 4381'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Strata Drlg.

Address Wichita, Kansas License No.

Operation Completed: Hour 4:45 A Day 14 Month 1 Year 1978

The above well was plugged as follows:

RTD 4381' 8 5/8 csg set 294' cwc 200 sk. Plg. Mat. 50-50 poz 6% total gel.

Gypped pits, circulated heavy mud, set 70 sk cmt plug at 550' thru drill pipe.

Heavy mud to 240' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid
bridge & 10 sk cmt plug to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION

JAN 16 1978

CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo Massey
Well Plugging Supervisor

DATE 1-17-78
INV. NO. 6588-U