

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

Form CP-3  
RECEIVED  
STATE CORPORATION COMMISSION  
6-4-68

MAR 22 1978

CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15-135-21138-0000 (of this well)

Operator's Full Name Mull Drilling Co., Inc.

Complete Address 415 Page Ct.-220 W. Douglas, Wichita, Kansas 67202

Lease Name Whitley Well No. 4

Location 150' SE of C. NW NE Sec. 24 Twp. 20 Rge. (E) (W) 23

County Ness Total Depth 4356'

Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Rockhold Engineering, Inc.

Address Box 698, Great Bend, Kansas License No. 670

Operation Completed: Hour 11:30 A Day 21 Month 3 Year 1978

The above well was plugged as follows:

Total Depth 4356' 8 5/8 csg set 285' cwc 200 sk.

4 1/2 csg set 4345' cw 100 sk cem.

Filled 4 1/2 csg W/sd (4356'-4300') dumped 4 sk cem W/dump bailer. (4300'-4265')

Cutoff & recovered 2450' of 4 1/2 csg.

Halliburton Cementing Co. mixed & pumped down 8 5/8 csg with 25 sk gel & water

W/100 lbs hulls, released 8 5/8 cementing plug & pumped 140 sk 50-50 poz 2%

& shutin. FPP 300 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]  
Well Plugging Supervisor

DATE 3-23-78  
INV. NO. 6984-W