

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAR 6 - 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Pickrell Drilling Company

Complete Address: 705 Fourth National Bank Bldg., Wichita, Kansas

Lease Name Harkness "C" Well No. 1

Location C SW SW Sec. 26 Twp. 20 Rge. 23 (E) (W) X

County Ness Total Depth 4370

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Co. Tools

Address: License No.

Operation Completed: Hour 12:30 P Day 4 Month 3 Year 1968

The Above well was plugged as follows:

RTD 4370' 8 5/8 csg set at 270' cwc 175 sc. Cem. Mat. 100 sc 50-50 poz cem. W/6% gel.

Gunned pits, circulated heavy mud, set cementing plug at 600' and displaced 70 sc cem.

thru drill pipe. Heavy mud to 240' set cementing plug and displaced 20 sc cement thru

drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base

of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 3/6/68
INV. NO. 7373-4