

WELL PLUGGING RECORD

Give All Information Completely
 Make Required Affidavit

COUNTY Rush SEC. 5 TWP. 17 RGE. 16 ~~XX~~W
 Location as in quarters or footage from lines:
 SW/SW/NW

Locate Well
 correctly on above
 Section Platt.

Lease Owner Frontier Oil Company
 Lease Name Honderick "B" Well No. #1
 Office Address 1437 N. Franklin - Russell, Ks. 67665
 Character of Well (Completed as Oil, Gas or Dry Hole): Gas
 Date Well Completed _____
 Application for plugging filed _____
 Plugging commenced October 28, 1982
 Plugging completed November 11, 1982
 Reason for abandonment of well or producing formation
Depelting

Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Paul Luthi

Producing formation _____ Depth to top _____ bottom _____ T.D. 3200'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8"	215'	NONE
				4 1/2"	3186'	1981.33'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Dumped sand to 2990' and four (4) sacks cement.
Shot pipe @2500', 2200' and 2000'.
Pulled forty-nine (49) joints 4 1/2" casing.
Squeezed well with four (4) sacks hulls, fifteen (15) sacks gel,
fifty (50) sacks cement, ten (10) sacks gel, one (1) sack
hulls, released plug and pumped one hundred (100) sacks 50/50
pozmix cement with 4% added gel and 3% calcium chloride.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Rockhold Engineering, Inc.


STATE OF KANSAS COUNTY OF BARTON, ss.

James W. Rockhold (~~employee of owner~~) or (~~owner or operator~~) of the
 above-described well, being first duly sworn on oath, says: That I have knowledge of the
 facts, statements, and matters herein contained and the log of the above-described well as
 filed and that the same are true and correct. So help me God.

(Signature) James W. Rockhold
 JAMES W. ROCKHOLD - Box 698 - Great Bend, Ks.
 (Address) 67530

SUBSCRIBED AND SWORN TO before me this 18th day of Nov., 1982

My Commission expires



Margaret Prosser
 RECEIVED
 STATE CORPORATION COMMISSION
 Notary Public

NOV 22 1982

CONSERVATION DIVISION
 Wichita, Kansas