

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RETURN  
K.A.R.-82-3-117

API NUMBER 15-165-20,598-00-00

LEASE NAME Janson "A"

WELL NUMBER #2

2310 Ft. from S Section Line

1350 Ft. from E Section Line

SEC. 7 TWP. 17S RGE. 16 (E) or (W)

COUNTY Rush

Date Well Completed 10/1967

Plugging Commenced 10/31/2001

Plugging Completed 10/31/2001

RECEIVED

NOV 16 2001

KCC WICHITA

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Coas. Div.  
office within 30 days.

LEASE OPERATOR Tengasco Inc.

ADDRESS P.O. Box 458

PHONE (785) 625-6374 OPERATORS LICENSE NO. 32278

Character of Well TA'd

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 10/26/2001 (date)

by Richard Lacey (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? Should be on file.

Producing Formation Topeka Depth to Top 3064 Bottom 3078 T.D. 3218

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Topeka	Gas	3064	3078	8.625	284	na cmt'd
				4.5	3218	na cmt'd

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from    feet to    feet each set.

Pulled tbq up to 3013 and pump 200# hulls, 15 sxs gel and 25 sxs cement.

Pull tubing up to 1200 (Anhy) circulate cement to surface. Pull all tubing

and pump cement down casing to top it off. Hook up to backside and pressure

up to five hundred pounds. Backside had cement.

Name of Plugging Contractor Allied Cementing License No.                     

Address Russell KS, 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Tengasco Inc.

STATE OF Kansas COUNTY OF Rush, ss.

Edgar L. Glassman (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.


(Signature) Edgar L. Glassman

(Address) P.O. Box 458 Hays KS 67601

SUBSCRIBED AND SWORN TO before me this 15<sup>th</sup> day of NOV., 2001

Linda K. Remondet  
Notary Public

My Commission Expires: 2/15/2004



OR