

15. Nos. 00228-0000

WELL PLUGGING RECORD

STATE OF KANSAS
STATE CORPORATION COMMISSION


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

OR

FORMATION PLUGGING RECORD

Strike out upper line
when reporting plug-
ging off formations.

NORTH



Locate well correctly on above
Section Plat

Rush County. Sec. 21 Twp 17S Rge. (E) 16 (W)
Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines. C. SW. SW. NW
Lease Owner. Westgate-Greenland Oil Company, et al
Lease Name. Ochs Well No. 1
Office Address. 1022 Union National Bank Building, Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole). dry hole
Date well completed. April 19, 1948
Application for plugging filed. April 19, 1948
Application for plugging approved. April 19, 1948
Plugging commenced. April 19, 1948
Plugging completed. April 19, 1948
Reason for abandonment of well or producing formation. dry hole

If a producing well is abandoned, date of last production. 19.
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? C. D. Stough, Great Bend, Kansas

Name of Conservation Agent who supervised plugging of this well. C. D. Stough, Great Bend, Kansas
Producing formation. Depth to top. Bottom. Total Depth of Well. 3750 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Surface		0	923	8 5/8"	923	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud to 920 feet. Set plug at 920 feet, put in 15 sacks cement and filled hole to 200' with heavy mud. Set plug at 200 feet and dumped in 15 sacks cement. Filled to 30 feet with heavy mud. Set plug at 30 feet and dumped in 10 sacks of cement which filled hole to cellar.

APR 24 1948

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to G. E. Bitler, c/o Westgate-Greenland Oil Company
Address. 1022 Union National Bank Building, Wichita 2, Kansas

STATE OF Kansas COUNTY OF Sedgwick, ss.
J. B. Stewart (employee of owner) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

J. B. Stewart


1022 Union National Bank Building, Wichita, Kans
(Address)

SUBSCRIBED AND SWORN to before me this 20th day of April, 1948.

Esther Russell

Notary Public.

My commission expires May 25, 1949



COMPANY: Westgate Greenland Oil Company
 CONTRACTOR: Jackson Drilling Corporation
 FARM: Ochs #1
 LOCATION: SW/4 SW/4 NW/4
 Section 21-17S-16W - Rush Co., Kansas
 COMMENCED: March 20, 1948
 COMPLETED: April 18, 1948
 ELEVATION: 2077

0	to	10	Surface clay
10	to	160	Lime & shale
160	to	250	Shells & shale
250	to	397	Shell & lime shell
397	to	500	Shale & shells
500	to	700	Sand
700	to	1195	Red bed
1195	to	1230	Anhydrite
1230	to	1385	Shale & salt shells
1385	to	1560	Shale & shells
1560	to	1619	Shell & sand
1619	to	1870	Shale
1870	to	1920	Lime shale
1920	to	1940	Shale
1940	to	2315	Lime
2315	to	2735	Lime & shale
2735	to	2785	Lime
2785	to	2860	Shale
2860	to	3280	Lime & shale
3280	to	3360	Lime
3360	to	3630	Lime & shale
3630	to	3680	Shale
3680	to	3685	Lime
3685	to	3715	Lime & sand
3715	to	3750	Arbuckle
		3750	T.D.

APR 24 1948

Set 923' 8 5/8" surface pipe. Cemented with 450 sacks cement - 2 sacks calcium chloride
 Dry and abandoned

C E R T I F I C A T E

I, Clare A. Stewart, do hereby certify that the above and foregoing is a true and correct copy of log of the Ochs #1, Section 21-17S-16W, Rush County, Kansas as reflected by files of the Jackson Drilling Corporation.

Clare A. Stewart
 Clare A. Stewart

Subscribed and sworn to before me, a Notary Public, within and for Johnson County, Kansas, this 27th day of April, 1948.

Dorothy J. Wilson
 Dorothy J. Wilson



My Commission expires November 30, 1950

APR 27 1948
 21 17 16W
 74 ✓