


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Rush County. Sec. 18 Twp. 17S Rge. 16W E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
C SE/4

Lease Owner Frontier Oil Company
Lease Name Schriener Well No. 1
Office Address 1720 KSB&T Bldg., Wichita, Kansas
Character of Well (Completed as Oil, Gas or Dry Hole)
Gas Well



Locate well correctly on above
Section Plot

Date Well completed 9-22 1965
Application for plugging filed 7-13- 1978
Application for plugging approved 7-14- 1978
Plugging commenced 8-16 1978
Plugging completed 8-16 1978
Reason for abandonment of well or producing formation
Depleted

If a producing well is abandoned, date of last production
January 1978

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey
Producing formation Depth to top Bottom Total Depth of Well 3648
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface				8 5/8	213	-0-
				4 1/2	3186	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mpa press 1200#
Shut in press 800#

Cement from 3000 to 3648
" " 0 to 400

Mixed 45 sx poz cement followed by 35 sx
gel. Released Plug and mixed 45 sx poz cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Allied Cementing, Russell, Kansas

STATE OF Kansas COUNTY OF Sedgwick, ss.
Richard D. Parker (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)


Russell, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 22nd day of August, 1978

Maxine V. Starr
Notary Public.

My commission expires 10-1-81



RECEIVED
STATE CORPORATION COMMISSION

AUG 23 1978

CONSERVATION DIVISION
Wichita, Kansas

DRILLERS LOG

Schriner No. 1

CASING RECORD:	COMPANY:	Frontier Oil Company	DESCRIPTION:
8 5/8" @ 213'	CONTRACTOR:	Red Tiger Drilling Company	C SE
w/135 sx cement	COMMENCED:	September 14, 1965	18-17S-16W
4 1/2" @ 3186'	COMPLETED:	September 22, 1965	Rush Co., Ks.
w/150 sx cement			ELEVATION: 2045 DF
			2048 RB
TOTAL DEPTH:			
3648'			

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Soil & Clay	0	40	
Shale & Lime	40	95	
Shale & Shells	95	550	
Dakota Sand	550	750	
Redbed & Shale	750	1155	
Anhydrite	1155	1192	
Shale & Shells	1192	2015	
Lime & Shale	2015	2380	
Shale & Shells	2380	2605	
Shale & Lime	2605	3260	
Lime	3260	3285	
Lime & Shale	3285	3355	
Lime	3355	3648	

I certify that this is a true and correct copy of the above log to the best of my knowledge.

FRONTIER OIL COMPANY

Maxine V. Starr
Maxine V. Starr

Subscribed and sworn to before me this 30th day of September, 1965.

Jean Hollan
Notary Public



My Commission Expires:
3-22-66

RECEIVED
STATE CORPORATION COMMISSION
JUL 14 1978
CONSERVATION DIVISION
Wichita, Kansas