

15-1165-30032-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Rush County. Sec. 16 Twp. 17S Rge. (E) 16(W)

Location as "NE/CNW/SW" or footage from lines C SE NW

Lease Owner Pickrell Drilling Company

Lease Name Brack Well No. 1

Office Address 705 4th Natl Bank Building, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed August 31, 19 65

Application for plugging filed August 31, 19 65

Application for plugging approved August 31, 19 65

Plugging commenced August 31, 19 65

Plugging completed August 31, 19 65

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation Depth to top Bottom Total Depth of Well 3634 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	352	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Heavy mud to 540', set plug, cemented with
20 sacks cement. Heavy mud to 240', set plug,
cemented with 20 sacks cement. Heavy mud to
40', set plug. Cemented with 10 sacks cement
to bottom of cellar. Plugged rat hole with
2 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
SEP 22 1965
CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Pickrell Drilling Company

Address 705 4th Natl Bank Building, Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

C. W. SEBITS

(owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

C. W. Sebits

705 4th National Bank Bldg, Wichita, Kansas

(Address)

SUBSCRIBED AND SWORN to before me this 7th day of September, 19 65

My commission expires June 21, 1966

Maxine Blackman
Maxine Blackman, Notary Public.



15-165-30032-0000

ROTARY DRILLING LOG

COMPANY: PICKRELL DRILLING COMPANY
705 4th Natl Bank Bldg.
Wichita, Kansas 67202

Rotary Drilling Commenced 8-21-65
Rotary Drilling Completed 8-31-65

LOCATION: BRACK No. 1, C SE NW Section 16-17S-16W, Rush County, Kansas.

CONTRACTOR: **PICKRELL DRILLING COMPANY**
Wichita, Kansas

CASING RECORD: (16 jts) 8 5/8" surface casing set at 352' cemented with 200 sacks cement. Circulated. Completed 10:45 P.M. August 21, 1965. No oil string run, D & A.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

60	Surface Soil & Clay	<u>C. F. S.</u>
352	Shale & Sand Stringers	3355
580	Shale	3370
955	Red Rock & Lime	3385
1620	Shale & Shells	3562
2025	Lime & Shale	3585
2200	Lime	3600
2555	Lime & Shale	3613
2745	Lime	3620
2985	Lime & Shale	3630
3450	Lime	3634
3490	Lime & Shale	
3562	Lime & Shale	<u>Slope Tests</u>
3634	Lime-Arbuckle-RTD	2000
		2500
		3000
		3500
		<u>S. L. M.</u>
		3077
		3362
		3587

RECEIVED
STATE CORPORATION COMMISSION
SEP 22 1965
CONSERVATION DIVISION
Wichita, Kansas

The undersigned, C. W. SEBITS, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY

By C. W. SEBITS Attorney-in-Fact

STATE OF KANSAS }
COUNTY OF SEDGWICK } ss.:

On this 17th day of September, 1965, before me the undersigned, a Notary Public, in and for the County and State aforesaid, personally appeared C. W. SEBITS, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: June 21, 1966

Maxine Blackman
Maxine Blackman, Notary Public