

15-165-00179-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

WELL PLUGGING RECORD

Rush County, Sec. 18 Twp. 17 Rge. (E) 16W

Location as "NE/CNWxSWx" or footage from lines SW SW SE

Lease Owner Brunson Production & Exploration

Lease Name Schriener Well No. 1

Office Address 333 1st Nat'l. Bank Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 12-15-55 19

Application for plugging filed " " " 19

Application for plugging approved " " " 19

Plugging commenced " " " 19

Plugging completed " " " 19

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well R. M Brundage

Producing formation Depth to top Bottom Total Depth of Well 3591 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	1159	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Gunned pits and circulated heavy mud into hole. Laid down DP. Filled hole to 300' of top. Poured 1/2 sack of hulls on top of fluid. Pushed plug to 300'. Poured 1/2 sak of hulls on top of plug & 20 sacks of well mixed cement. Filled hole to 40' of top & poured 1/2 sack of hulls on top of plug. Pushed plug to 40'.

Poured 1/2 sack of hulls on top of plug & 10 sacks of well mixed cement. Plug secured with two strands of .066 Howco Steel line.

12-27-55

Name of Plugging Contractor Brunson Production & Exploration, Inc.
Address 333 1st National Bank Bldg., Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
I, Ralph B. McLaughlin (employee of owner) or (owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.



(Signature) Ralph B. McLaughlin

(Address)

SUBSCRIBED AND SWORN to before me this 17th day of December 19 55

My commission expires Dec. 31, 1958

Donna L. Riley Notary Public.



BRUNSON PRODUCTION & EXPLORATION, INC.

WELL: BRUNSON # 1
 COMMENCED: 12-3-55
 COMPLETED: 12-15-55

SW 34 SE
 SEC. 18-17-10
 Rush County

CASING: 11 5/8" 80# CO. Brnd thd 2 1/2"
 Depth: 3591

Elevation: 2034 RB
 Contractor: Brunson
 Production & Exp.

STRATA	DEPTH		TOPS
Clay	75	Anhydrite-	1128
Shale	290	Lea'ner3	3215-1221
Red Sand & shale	310	Lansing-NC	3510-1276
Pyrite & sand	475	Granite wash	3540-1506
Shale	670		
Red Sed	1125		
Gyp	1132		
Anhydrite	1128		
Shale	1490		
Shale & shells	1610		
Salt & shale	1720		
Shale & shells	1840		
Broken Lime	1960		
Shale	2660		
Lime & shale	2962		
Shale	3065		
Broken lime	3103		
Lime	3155		
Lime & shale	3225		
Lime	3345		
Granite wash	3540		
Granite	3591		
Total Depth	3591		

I hereby certify that the above is a true and correct log of said well as reflected by the daily drilling reports.

BRUNSON PRODUCTION & EXPLORATION, INC.

Ralph B. McLaughlin
 Ralph B. McLaughlin, Sec-Treas.

Signed and sworn to in my presence this 20th day of December, 1955, by Ralph B. McLaughlin-Secretary-Treasurer of the Brunson Production & Exploration, Inc., a Corporation in the State of Kansas.

Donna L. Riley
 Donna L. Riley, Notary Public

My commission expires December 31, 1956.

PLUGGING
 DATE 12-18-55 BY B/W
 TIME 24 LTR 28