

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-22585-00-00
Spot: SENWNW Sec/Twnshp/Rge: 28-20S-10W
4328 feet from S Section Line, 4290 feet from E Section Line
Lease Name: THOMPSON Well #: 2
County: RICE Total Vertical Depth: 3353 feet

Operator License No.: 5210
Op Name: LEBSACK OIL PRODUCTION INC.
Address: PO BOX 354
CHASE, KS 67524

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2000		
CIBP	5.5	2480		
DVT	5.5	2114		170 SX
PC		2114		170 SX CMT
PROD	5.5	3341	903	150 SX
SURF	8.625	264		
T1	2.375	1991		

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: - 09/15/2012 2:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKES TESTING & SALVAGE, INC. Phone: (620) 938-2943

Proposed Plugging Method: SEE BELOW

Plugging Proposal Received By: VIRGIL CLOTHIER Witness Type: PARTIAL
Date/Time Plugging Completed: 09/05/2012 4:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, PULL RODS & TUBING. HAD LOG TECH INC. OF KS ATTEMPT TO SET CIBP @ 2050'--STACKED OUT @ 1995'--CIBP EVIDENTLY ALREADY SET. HAD LOG TECH INC. OF KS SET CIBP @ 1360' AND CAP WITH 2 SX'S CEMENT. TOP OF CEMENT ON BACKSIDE OF CASING--UP ABOVE 1190'--AMT OF STRETCH INDICATED. CUT CASING OFF @ 903'--PULL TO 850' AND PUMP 35 SX'S CEMENT. PULL CASING TO 315' AND CIRCULATE CEMENT TO SURFACE. PULL CASING OUT AND TOP OFF.

Perfs:

Top	Bot	Thru	Comments
2521	2537	CSG	
2506	2524	CSG	
2410	2414	CSG	
2252	2254	CSG	
2094	2098	CSG	
1410	1414	CSG	

RECEIVED
SEP 12 2012
KCC WICHITA

Remarks: 60-40 POZ, 4% GEL. LOG TECH INC. OF KS 7184. COPELAND C-38657. WELL HAD BEEN DENIED TA STATUS -- DUE TO HFLD.

Plugged through: CSG

District: 02

Signed Virgil Clothier
(TECHNICIAN) 9/20/12